St Huberts Close, Gerrards Cross

Specification applicable to all house types A–E unless stated otherwise in the plot schedule (section 4)

1. Kitchens

Units	Shaker-style painted units with soft-close hinges; maple-effect option on type E
Worktops	20 mm quartz with upstand; 1½ bowl stainless steel undermount sink
Appliances	Integrated oven, combination microwave, induction hob, extractor, fridge-freezer and dishwasher

2. Bathrooms and en-suites

Family bathroom	White suite with bath, thermostatic shower over bath and glass screen
En-suites	**All en-suites are fitted with walk-in showers with low-profile trays and glass screens. No en-suite has a bath.**
Tiling	Full height to wet areas; half height elsewhere; porcelain floor tiles
Sanitaryware	Wall-hung WCs with concealed cisterns; chrome fittings throughout

3. Heating, electrical and external

Heating	Gas-fired condensing boiler with radiators; underfloor heating to ground floor of types D and E
Electrical	LED downlights to kitchen and bathrooms; USB sockets to kitchen and bedrooms
Garaging	Double garage to types C, D and E; single garage to types A and B
EV charging	7 kW charge point to every garage

This schedule describes the standard specification for the development. Purchasers should check the plot schedule and the individual property, as finishes may vary between plots and may have been altered by subsequent owners.

4. House types and plot schedule

Type	Name	Bedrooms	Bathrooms (incl. en-suite)	Receptions	Garage	GIA sq ft
A	The Bulstrode	3	2	2	Single	1,420
B	The Chalfont	4	2	2	Single	1,760
C	The Denham	4	2	2	Double	2,098
D	The Fulmer	5	3	3	Double	2,512
E	The Hedgerley	5	3	5	Double	2,848

Plot / No.	House type	Handed	Notes
51	C	No	—
53	D	Yes	—
55	C	Yes	—
57	D	No	Conservatory added (owner)
59	E	No	Principal en-suite and guest en-suite as standard type E
61	E	Yes	—

Approval. Issued for sales information. Revision C supersedes Revision B (2 March 2026): updated EV charging and kitchen worktop wording.

Signed for Chiltern Vale Developments Ltd

M. Ashdown

Marcus Ashdown, Technical Director · 15 September 2026